



I-210 BRIDGE BI-WEEKLY CONSTRUCTION NOTICE AUGUST 5 - 18, 2012



WHAT: Construction activity may require occasional lane closures of the eastbound I-210 Freeway.

WHEN: Occasional lane closures of up to three eastbound lanes may take place during this bi-weekly period. These lane closures will start no earlier than 10 p.m. and end by 1 p.m. the following day. No full closures of the eastbound I-210 Freeway are scheduled for this bi-weekly period.

WHERE: Eastbound lanes of the I-210 Freeway, between Rosemead Blvd. and Santa Anita Ave.

WHAT TO EXPECT: During the next two weeks, crews will start removing the exterior forms (shown in the photo below) for the bridge superstructure, which will slowly begin to reveal the bridge surfaces. Additionally, crews will also perform a process known as post-tensioning that will strengthen the bridge superstructure. In this process, several high-strength steel tendons that run the entire length of the bridge will be pulled tight by powerful hydraulic jacks and anchored against each end of the bridge. The taut steel tendons will act to compress the bridge from end to end, which adds significant strength to the superstructure.

Construction schedules are subject to change for various reasons including but not limited to weather conditions and unforeseen delays. Please note that other construction projects are also affecting the Arcadia stretch of the I-210 Freeway. To learn more about upcoming ramp and lane closures from these projects, be sure to visit the websites listed below.



Bridge exterior forms during installation in mid-April 2012

Curing blankets covering the new bridge deck

Toll-Free Project Hotline: 855-446-1160

For I-210 Bridge information:

- www.foothillextension.org

For other Arcadia area projects:

- www.go511.com
- <http://www.dot.ca.gov/dist07/>
- <http://caltransd7info.blogspot.com/>

Questions? Comments? Call...

For I-210 Bridge Construction Info:

Joe Hernandez, Community Liaison
Skanska USA Civil
(626) 593-4040
joe.hernandez@skanska.com

For Foothill Extension Project Info:

Sylvia Beltran, Community Outreach Coordinator
Construction Authority
(626) 305-7012
sbeltran@foothillextension.org